



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 26 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
11-26-73

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: A. Scott Ritchie,

Complete Address: 412 Union Center Building, Wichita, Kansas.

Lease Name: Ninemire Well No. 1

Location: CSW-SE Sec. 12 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3915' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

222'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 825'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 110 Cu. Ft. cement thru DP. Pull DP to 235' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Draper  
Conservation Division Agent