



15-065-20469-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 26 1971  
CONSERVATION DIVISION  
Wichita, Kansas

17-26-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. A. G. Radke of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Radke guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company,

Complete Address: 217 North Water, Wichita, Kansas.

Lease Name: Ninemire Well No. B-1-V

Location: SW-SE-SW Sec. 14 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3740' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Radke was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 800':

Circulate hole with heavy mud. Pull DP to 1025' and displace 100 Sx.  
cement thru DP. Pull DP to 280' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*R. L. Daniels*  
Conservation Division Agent