

DISTRICT CONSERVATION AGENT'S REPORT

R

15-065-03364-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 59-28

LOCATION NW SE SE

SEC. 9 TWP. 9 RGE. 22

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Rich

Operator Gulf Oil Co Address Box 2233 Wichita, Kans

Field _____ County Graham

Total Depth 3919 Feet.

Plugging Contractor Morgan Well Pulling Service & Halliburton Co

Plugging Contractor's License No. 43

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 409' circulated with cement - 5 1/2" 3901 with 100 sax
cement behind. P.B. to 3913'.

Filled with chat to 3890', set 4 sax cement with dump bailer, pulled
3100' 5 1/2" to 1000', circulated hole with heavy mud through 5 1/2" (125
Bbls mud), displaced 30 sax cement through 5 1/2" at 650', heavy mud to
300', displaced 30 sax cement through 5 1/2" at 300', heavy mud to
60', set rock and 20 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

John Hanna

By *E. R. Lott*
District Conservation Agent

Date 12-16-57

RECEIVED
STATE CORPORATION COMMISSION

DEC 19 1957 12-19-57

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 9 T. 9 R. 22
BOOK PAGE 59 LINE 28