

KANSAS

Form CP-3
Rev. 6-26-62

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20147-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1968
CONSERVATION DIVISION
Wichita, Kansas

6-10-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company, Incorporated,

Complete Address: 410 Fourth National Bank Building, Wichita, Kansas.

Lease Name Rice Estate Well-No. A-1

Location NE-SE Sec. 9 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 2580'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Omega Drilling, Incorporated,

Address: 427 Union Center Bldg., Wichita, Kansas. License No.

Operation Completed: Hour 5:30AM Day 6 Month 6 Year 1968

The Above well was plugged as follows:

223'--8 5/8" Surface pipe, cement circulated with 185 Sx.
Top of Dakota Section @ 840'.

Circulated hole with heavy mud. Pulled DP to 1065' and displaced 100 Sx. cement thru
DP from 1065' to 740'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Decker*
Well Plugging Supervisor

INVOICED

DATE 6/10/68
INV. NO. 4922-u