

15-065-20342-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*24*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 1 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
*7/1/70*

Operator's Full Name Murfin Drilling Company.

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Casey Jones Well No. 2

Location NW-SE-NE Sec. 1 Twp. 9 Rge. (E) (W)23

County Graham Total Depth 3830'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Above

Address      License No.     

Operation Completed: Hour 5:30 PM Day 28 Month 6 Year 1970

The above well was plugged as follows:

196'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 100 Sx. cement thru  
DP from 1050' to 725'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from  
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 7/1/70

INV. NO. 2148-W