

KANSAS

Form CP-3
Rev. 6-4-68

KS STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20280-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

12-1-69
RECEIVED
STATE CORPORATION COMMISSION
DEC 1 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Mildrexter Well No. 1

Location NW-NW-SW Sec. 2 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3810'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 4:00 PM Day 27 Month 11 Year 1969

The above well was plugged as follows:

167'--8 5/8" Surface casing, cement circulated with 125 Sx.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx. cement thru
DP from 975' to 650'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from
185' to 125'. Pulled DP, set bridge @ 40' w with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 12/2/69
INV. NO. 957-W