

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-065-20671-00-00

5-3-74  
RECEIVED  
STATE CORPORATION COMMISSION

MAY 3 - 1974

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Davignon Well No. 1

Location NW-SE-SW Sec. 6 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3740'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 12:15 PM Day 1 Month 5 Year 1974

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 110 Cu. Ft. cement  
thru DP from 1175' to 850'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 5/8/74  
INV. NO. 9058-W