

DISTRICT CONSERVATION AGENT'S REPORT

*R*

15-065-00956-00-00

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SE SE NE

SEC. 7 TWP. 9 RGE. 23

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. B-1 Lease Harvey "B"

Operator Imperial<sup>oil</sup> of Kansas Inc. Address 905 J.K. Natl Bldg,  
Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3865 Feet.

Plugging Contractor same

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 223' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug  
at 600', displaced 25 sax cement through drill pipe, heavy mud  
to 215', set cementing plug and displaced 15 sax cement through  
drill pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls  
and 10 sax cement to bottom cellar.

*Edward Kelly*

District Conservation Agent

Date 8-19-57

RECEIVED  
STATE CORPORATION COMMISSION  
820-57  
AUG 20 1957

PLUGGING  
FILE SEC. 7 T. 9 R. 23W  
BOOK PAGE 39 LINE 2

CONSERVATION DIVISION  
Wichita, Kansas