

15-065-20271-00-00

Form CP-3
Rev. 6-4-68

24

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1969
CONSERVATION DIVISION
Wichita, Kansas

10-30-69

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name McVey Well No. 1

Location NE-SE-NW Sec. 10 Twp. 9 Rge. XX (E) (W) 23

County Graham Total Depth 3845'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 6:30 PM Day 26 Month 10 Year 1969

The above well was plugged as follows:

188'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx. cement thru
DP from 975' to 650'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215'
to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/30/69
INV. NO. 748-U

Signed: *W. L. Dehels*
Well Plugging Supervisor