

2

DISTRICT CONSERVATION AGENT'S REPORT

15-065-00694-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 41-19

LOCATION NW NW NW

SEC. 12 TWP. 9 RGE. 23

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Mildrester

Operator Petroleum Management Address 1019 Cent Bldg Wichita.

Field _____ County Graham

Total Depth 3860 Feet.

Plugging Contractor E & L Pipe Drilling Co & Halliburton Co

Plugging Contractor's License No. 249

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 175' circulated with cement - 5 1/2" 3860' with 125 sax
cement behind - Perf at 3816'.

Filled with sand to 3800', set 4 sax cement with dump bailer, pulled

1845' 8 5/8" to 1100', circulated hole with heavy mud (70 sax Gal),

Displaced 25 sax cement through 5 1/2" at 700', heavy mud to 160',

displaced 15 sax cement through 5 1/2" at 160', heavy mud to 35', set

rock and 10 sax cement to bottom cellar.

Mudding and Cementing by Halliburton Cementing Co.

Leon Petty

District Conservation Agent

Date 10-11-57

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1957
CONSERVATION DIVISION
WICHITA, KANSAS

10-15-57

PLUGGING
FILE SEC 12 T 9 R 23W
BOOK PAGE 41 LINE 14