

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-065-02261-00-00

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW NE NW

SEC. 12 TWP. 9 RGE. 23

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Mildrexter

Operator C & G Drg Co Address Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3869 Feet.

Plugging Contractor same

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 223' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at

700', displaced 20 sax cement through drill pipe, heavy mud to

210', set cementing plug and displaced 15 sax cement through drill

pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10

sax cement to bottom cellar.

Edson Perry

District Conservation Agent

Date 12-1-57

RECEIVED  
STATE CORPORATION COMMISSION  
12-4-57  
DEC 4 1957  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 12 T 9 R 23  
BOOK PAGE 65 LINE 40