

15-065-20638-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

11-26-73  
RECEIVED  
STATE CORPORATION COMMISSION  
NOV 26 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name A. Scott Ritchie,  
Complete Address 412 Union Center Building, Wichita, Kansas.  
Lease Name Ninemire Well No. 1  
Location CSW-SE Sec. 12 Twp. 9 Rge. (E) (W) 23  
County Graham Total Depth 3915'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Dreiling Oil, Incorporated,  
Address R. R. #2, Victoria, Kansas. License No.         
Operation Completed: Hour 1:00 PM Day 18 Month 11 Year 1973

The above well was plugged as follows:

222'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 110 Cu. Ft. cement  
thru DP from 1050' to 725'. Pulled DP to 235' and displaced 30 Cu. Ft. cement thru  
DP from 235' to 160'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

**INVOICED**

I hereby certify that the above well was plugged as herein stated.

DATE 11/29/73

INV. NO. 8217-W

Signed: W. L. Dickels  
Well Plugging Supervisor