

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20469-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1971
CONSERVATION DIVISION
Wichita, Kansas

7-26-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Company,

Complete Address 217 North Water, Wichita, Kansas.

Lease Name J. A. Ninemire Well No. B-1-V

Location SW-SE-SW Sec. 11 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3740'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Garvey Drilling Company,

Address Box #1164, Great Bend, Kansas. License No. _____

Operation Completed: Hour 1:45 AM Day 21 Month 7 Year 1971

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 100 Sx. cement thru
DP from 1025' to 700'. Pulled DP to 280' and displaced 25 Sx. cement thru DP from
280' to 205'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Deibel
Well Plugging Supervisor

INVOICED

DATE 7-29-71

INV. NO. 4060-W