

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15065-01926-00-00

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1974

CONSERVATION DIVISION
Wichita, Kansas

12-13-74

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sun Oil Company

Complete Address 800 Security Life Bldg., Denver, Colorado 80202

Lease Name E. Davignon Well No. 33

Location N/2 SW SW Sec. 11 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3774'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Crowe Pipe Pulling

Address Hays, Kansas License No. 733

Operation Completed: Hour 11:30 A Day 12 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 3774' 10 3/4 csg set at 290' cwc 150 sk.

5 1/2 csg set at 3749' cw 125 sx cem.

DV tool set at 1928' cw 200 sk.

Filled 5 1/2 csg W/sd (3774-3740) dumped 4 sk cem W/dump bailer. (3740-3710)

Cutoff & recovered 765' of 5 1/2 csg.

Pumped down 10 3/4 csg with 25 sk gel & water W/300 lbs hulls -80 sk cem -15 sk

gel & water -released 10 3/4 pig & pumped 60 sk cem. by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Eric J. Mueser
Well Plugging Supervisor

DATE 12/16/74

INV. NO. 477-W