

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-065-20615-00-00

RECEIVED  
STATE CORPORATION COMMISSION

DEC 13 1974

CONSERVATION DIVISION  
Wichita, Kansas

12-13-74

Operator's Full Name Sun Oil Company

Complete Address 800 Security Life Bldg., Denver, Colorado 80202

Lease Name Davignon Well No. 7

Location NE NW SW Sec. 11 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3903'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Crowe Casing Pulling

Address Hays, Kansas 67601 License No. 733

Operation Completed: Hour 1 P Day 12 Month 12 Year 1974

The above well was plugged as follows:

Total depth 3903' 8 5/8 csg set at 293' cwc 275 sk.

5 1/2 csg set at 3900' cw 150 sk cem.

5 1/2 csg PBD 3884' With pfs (3758-3782)

Set 5 1/2 wood plug at 3700' -poured 20' sd -dumped 4 sx cem W/dump bailer. (3700-3650)

Cutoff & recovered 2650' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk cem. -10 sk

sk gel & water -released 8 5/8 plug & pumped 50 sk cem. by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Munsey  
Well Plugging Supervisor

INVOICED

DATE 12/16/74

INV. NO. 478-w