

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-01453-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1974

CONSERVATION DIVISION
Wichita, Kansas

10-21-74

Operator's Full Name Barnett Oil Company,

Complete Address 411 First National Bank Building, Wichita, Kansas.

Lease Name Andreson ^{RCC} _{ZAD} Well No. B-2

Location NW-SE-NW Sec. 21 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3789'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Incorporated,

Address Box #486, Ellinwood, Kansas. License No. 462'

Operation Completed: Hour 12:45 PM Day 15 Month 10 Year 1974

The above well was plugged as follows:

150'--8 5/8" Surface casing, cement circulated with 125 Sx.
3784'--5 1/2" Production casing cemented on bottom with 125 Sx. (Open-Hole Completion).

Sanded well back to 3770' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (912') and squeezed well initially with 5 sacks hulls and 12 sacks gel, followed with 110 Cu. Ft. cement from 925' to 600' then 11 sacks gel from 600' to 170' and followed with 30 Cu. Ft. cement from 170' to 100' then 2 sacks gel from 100' to 20' and finally 10 Cu. Ft. cement from 20' to base of cellar. Maximum pump-in pressure-300#. FSIP-100#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. D. [Signature]
Well Plugging Supervisor

INVOICED

DATE 10/23/74
INV. NO. 146-W