

DISTRICT CONSERVATION AGENT'S REPORT

B

13-005-02918-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE NE SE

SEC. 21 TWP. 9 RGE. 21 W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Felt

Operator Barnett Oil Co Address 417 1st Natl Bk Bldg

Field _____ County Graham

Total Depth 3779 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 166' circulated with cement - 5 1/2" at 3775' with 125
sax cement behind.

Filled with chat to 3765' set 4 sax cement with dump bailer,
shot pipe and circulated hole with Aquagel and hulls, pulled
1000' 5 1/2" - mud to 166', set rock and 20 sax cement, mud to
30', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1953

CONSERVATION DIVISION
Wichita, Kansas

3-18-53

Edson Pease
District Conservation Agent

Date 3-10-53

PLUGGING
FILE SEC 21 T 9 R 21 W
BOOK PAGE 85 LINE 24