

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-03398-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1974
10-21-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Barnett Oil, Incorporated,

Complete Address 411 First National Bank Building, Wichita, Kansas.

Lease Name Andreson ^{KCC} _{R-2AD} Well No. B-6

Location SE-SW-NW Sec. 21 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3826'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Incorporated,

Address Box #486, Ellinwood, Kansas. License No. 462

Operation Completed: Hour 11:00 AM Day 15 Month 10 Year 1974

The above well was plugged as follows:

137'--8 5/8" Surface casing, cement circulated with 125 Sx.
3820'--5 1/2" Production casing cemented on bottom with 125 Sx. (Open Hole Completion).

Sanded well back to 3800' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
792') and squeezed well initially with 5 sacks hulls and 11sacks gel, followed with
110 Cu. Ft. cement from 975' to 650' then 12 sacks gel from 650 to 170' and followed
with 30 Cu. Ft. cement from 170' to 100' then 2 sacks gel from 100' to 20' and finally
10 Cu. Ft. cement from 20' to bottom of cellar. (Mudding & cementing by Allied Cmtg.).

I hereby certify that the above well was plugged as herein stated.

Signed: A. G. Drehele
Well Plugging Supervisor

INVOICED

DATE 10/23/74
INV. NO. 147-W