

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20254-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 22 1969  
CONSERVATION DIVISION  
Wichita, Kansas

9-22-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Company,

Complete Address 217 North Water, Wichita, Kansas.

Lease Name Lillie Gosselin Well No. 1-V

Location NE-NE-NW Sec. 10 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3693'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Kansas. License No.       

Operation Completed: Hour 7:15 AM Day 18 Month 9 Year 1969

The above well was plugged as follows:

251'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 525'.

Circulated hole with heavy mud. Pulled DP to 740' and displaced 100 Sx. cement thru  
DP from 740' to 415'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from  
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/22/69  
INV. NO. 515-W

Signed: W. L. Nichols  
Well Plugging Supervisor