

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20282-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1969
CONSERVATION DIVISION
Wichita, Kansas

12-2-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Tilco et al,

Complete Address 200 Sutton Place, Wichita, Kansas.

Lease Name Desair Well No. 1

Location NE-SW-NE Sec. 10 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3780'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 7:00 AM Day 28 Month 11 Year 1969

The above well was plugged as follows:

243'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 550'.

Circulated hole with heavy mud. Pulled DP to 775' and displaced 100 Sx. cement thru
DP from 775' to 450'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/2/69
INV. NO. 949-4

Signed: W. L. Pechels
Well Plugging Supervisor