

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 2 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
4-2-74

15-065-20659-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Continental Oil Company,

Complete Address P. O. Box #267, Great Bend, Kansas.

Lease Name E. Clack Well No. 4

App. C.E. 1/2 NE SW  
Location 2090' FSL and 2310' FWL Sec. 10 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3736'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor John O. Farmer, Incorporated,

Address 370 W. Wichita, Russell, Kansas. License No.       

Operation Completed: Hour 2:30 PM Day 29 Month 3 Year 1974

The above well was plugged as follows:

2 1/2" -- 8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 625'.

Circulated hole with heavy mud. Pulled DP to 850' and displaced 110 Cu. Ft. cement  
thru DP from 850' to 525'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru  
DP from 250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. S. Dickels  
Well Plugging Supervisor

DATE 4/4/74

INV. NO. 8887-W