

15-065-01493-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 113-18

LOCATION NW NW SW

SEC. 24 TWP. 9 RGE. 21

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Barry

Operator British-American Address Box 3187 Oklahoma City

Field _____ County Rooks

Total Depth 3733 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1690' circulated with 450 sax cement.

5 1/2" at 3712' with ~~4xx~~ 200 sax cement behind.

Filled with sand to 3700', set 4 sax cement with dump

bailer, pulled 2400' 5 1/2", filled with mud to 300', set rock

and 20 sax cement, mud to 35', set rock and 10 sax cement

to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1953

CONSERVATION DIVISION
Wichita, Kansas

7-18-53

PLUGGING
FILE SEC 24 T 9 R 21
BOOK PAGE 113 LINE 18

John Kelly
District Conservation Agent
Date 7-14-53