

DISTRICT CONSERVATION AGENT'S REPORT

15-065-02279-00-00

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 104-23

LOCATION SE NE SE

SEC. 24 TWP. 9 RGE. 21 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Flora Barry

Operator Skelly Oil Co Address Russell, Kans

Field _____ County Graham

Total Depth 3835 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 299' circulated with cement - 5 1/2" at 3827.

Plastic and Lane wells plugs to 3630' - Perforations at

3609' - Chat to 3605' and 5 sax cement - Heavy mud to 299',

wood plug, rock bridge and 15 sax cement - Heavy mud to

35', wood plug, rock bridge and 10 sax cement.

2656', of 5 1/2" pulled.

RECEIVED

AUG 16 1949

8-16-49

PLUGGING
FILE SEC 24 T 9 R 21 W
BOOK 104 LINE 23

STATE CORPORATION
COMMISSION
KANSAS
District Conservation Agent

Date 8-9-49