

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 2 1975  
42-75  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-065-02880-0000

Operator's Full Name Continental Oil Company  
Complete Address 3535 N.W. 58th Street Oklahoma City, Okla. 73112  
Lease Name Drumm Comm. Co Well No. # 5  
Location C-SE-NE-SE Sec. 9 Twp. 9 Rge. 21 (E) (W) X  
County Graham Total Depth 3671  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Pipe Pullers Inc.  
Address Box 128 Ellinwood Ks. License No. 462  
Operation Completed: Hour 11:00 PM Day 31 Month March Year 1975

The above well was plugged as follows:

K.B. 2200, Oak Top 1550', SP. 382' of 10 3/4" cwc. 225 sx cem  
7" casing set @ 3666' w/200 sx cem. Top Perf. 3502' Plug Back  
3616'. Bottom Plug set @ 3460' w/25' sand + 45x cem.  
Recovered 795' of 7" casing. Pumped down 10 3/4" casing  
4 sx Hells, 17 sx Gel, 100 sx cem 50/50 permix 6% Gel,  
8 sx Gel, Release Plug. +100 sx.cem. 50/50 Permox 6%  
Closing Pres. 150 lbs.  
Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Gilbert Balthazar  
Well Plugging Supervisor

INVOICED

DATE 4/2/75

INV. NO. 1108-w