

DISTRICT CONSERVATION AGENT'S REPORT

15-065-02881-00-00

*R*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 150-26

LOCATION SW SW SE

SEC. 9 TWP. 9 RGE. 21

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Drumm

Operator Morganstern & Specter Address Russell, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3708 Feet.

Plugging Contractor Arnett Pipe Pulling

Plugging Contractor's License No. 265

Address \_\_\_\_\_  
(Describe briefly the manner in which the well was plugged)

8 5/8" at 208' circulated with cement - 5 1/2" at 3700' with 150  
sax cement behind.

Filled with sand to 3690', set 4 sax cement with dump bailer,  
pulled 1250' 5 1/2" - mud to 208', set rock and 15 sax cement,  
mud to 35', set rock and 10 sax cement to bottom cellar.

**PLUGGING**  
FILE SEC. 9 T. 9 R. 21W  
BOOK PAGE 150 LINE 26

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 31 1955  
CONSERVATION DIVISION  
Wichita, Kansas

*Edw. Hett*  
District Conservation Agent  
Date 10-26-55

10-31-55