

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20289-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1969
CONSERVATION DIVISION
Wichita, Kansas

12-11-69

Operator's Full Name Tilco, et al,

Complete Address 200 Sutton Place, Wichita, Kansas.

Lease Name McClellan Well No. 1

Location NW-SW-NE Sec. 28 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3940'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated

Address Box #186, Great Bend, Kansas. License No.

Operation Completed: Hour 9:00 PM Day 5 Month 12 Year 1969

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 759'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx, cement thru
DP from 975' to 650'. Pulled DP to 215' and displaced 25 Sx, cement thru DP from 215'
to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx, cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/11/69

INV. NO. 1019-10