

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-01023-06-02

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 22 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
6-22-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name D. G. Hansen Estate,

Complete Address Box #187, Logan, Kansas.

Lease Name Brown Estate Well No. 3

Location SE-SE-SW Sec. 31 Twp. 9 Rge. (E) (W)21

County Graham Total Depth 3871'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:00 PM Day 18 Month 6 Year 1970

The above well was plugged as follows:

121'--8 5/8" Surface casing, cement circulated with 125 Sx.  
3867'--5 1/2" Production casing cemented on bottom with 100 Sx. DV tool set @ 1778'  
with 390 Sx. cement, cement circulated. No plug back, no perforations.

Squeezed well with initially with 1 sack-hulls and followed with 25 Sx. cement then  
25 sacks gel and followed with 40 Sx. cement then 2 sacks gel and finally 10 Sx. cement.  
Maximum pump-in pressure--1000#. Final shut-in pressure--500#.

(mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 6/22/70  
INV. NO. 2086-W