

R

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-01141-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 15 1964  
12-15-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Morgenstern & Specter, Incorporated,

Complete Address: Box #661, Russell, Kansas.

Lease Name C. Smith Well No. A-1

Location CSW-SW-SE Sec. 31 Twp. 9 Rge. (E) (W)21

County Graham Total Depth 3885

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 11:00AM Day 12 Month 12 Year 1964

The Above well was plugged as follows:

211'--8 5/8" Surface pipe, cement circulated.

3881'--5 1/2" Production casing cemented with 100 Sx.

Well squeezed in the Dakota Sands.

Sanded well back to 3870' and set 5 Sx. cement with dump bailer.

Found fluid level @ 1370'. Filled with heavy rotary mud to 600', set rock bridge and 6 Sx. cement to 550'. Shot 5 1/2" @ 300', pulled 5 1/2" and filled hole to bottom of cellar With 5 to 1 Redi-Mix. (Used 3 1/2 yards Redi-Mix)

(Recovered 300' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 12-15-64  
INV. NO. 349-W

Signed: H. L. Deibel  
Well Plugging Supervisor