

KANSAS

28

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20426-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1971
CONSERVATION DIVISION
Wichita, Kansas

4-16-71

Operator's Full Name Pickrell Drilling Company
Complete Address 705 Fourth National Bank Building, Wichita, Kansas.
Lease Name Worland Well No. 1
Location CNW-SE Sec. 3 Twp. 9 Rge. (E) (W) 22
County Graham Total Depth 3838'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above

Address License No.

Operation Completed: Hour 10:00 PM Day 13 Month 4 Year 1971

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 875' and displaced 100 Sx. cement thru
DP from 875' to 550'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Pickrell
Well Plugging Supervisor

INVOICED

DATE 4/16/71

INV. NO. 3560-W