

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1973

CONSERVATION DIVISION
Wichita, Kansas

12-26-73

15-065-20647-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Murfin Drilling Company and Sam G. Harrison,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Bassett Well No. 1

Location NW-SW-SW Sec. 3 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3893'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address Above License No.

Operation Completed: Hour 6:45 Pm Day 17 Month 12 Year 1973

The above well was plugged as follows:

207'--8-5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 875' and displaced 110 Cu. Ft. cement
thru DP from 875' to 550'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

INVOICED I hereby certify that the above well was plugged as herein stated.

DATE 12/28/73

Signed: H. L. Dickels
Well Plugging Supervisor

INV. NO. 8339-W