

STATE OF KANSAS
 STATE CORPORATION COMMISSION

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 800 Bittling Building
 Wichita, Kansas


OR
FORMATION PLUGGING RECORD

Strike out upper line
 when reporting plug-
 ging off formations.

Graham County. Sec. 11 Twp. 9S Rge. (E) 21 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NW SE
 Lease Owner Hinkle Oil Co. & Franco Central Oil Company
 Lease Name Eichman Well No. 1
 Office Address 914 Union National Bank Building, Wichita, Kansas.
 Character of Well (completed as Oil, Gas or Dry Hole) dry
 Date well completed 12-21-47 19
 Application for plugging filed 12-21-47 19
 Application for plugging approved 12-21-47 19
 Plugging commenced 12-21-47 19
 Plugging completed 12-21-47 19
 Reason for abandonment of well or producing formation.

NORTH



Locate well correctly on above
 Section Plat

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced? Yes

Name of Conservation Agent who supervised plugging of this well Mrs. Kerr
 Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	199	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.

Filled with mud to 199'
 Set wood plug at 199'
 Cemented with 15 sack cement
 Filled with mud to 40'
 Set wood plug at 40'
 Cemented with 10 sack cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Hinkle Oil Company 914 Union National Bank Building
 Address Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

J. B. Hinkle

(owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Hinkle

(Address)

day of December 1947

Muriel A. Lipton

Notary Public.

DEC 29 1947

SUBSCRIBED AND SWORN to before me this 26th day of

My commission expires Jan. 17, 1950

22-237 7-47-10M

PLUGGING
 FILE SEC 11 T 9 R 21W
 BOOK PAGE 6 LINE 27

12-29-47

15-065-02472-00-00

Well No. 1, NW SE 1/4, S 11, T 9, R. 21W, Graham Co., Kansas.

Coring
8 1/2 1947

Operator: Hinkle Oil Company & Franco Central Oil Co.
Contractor: J. B. Hinkle,
Commenced Dec. 9, 1947 Completed Dec. 21, 1947.
Elevation 2185

0	199	surface
199	870	shale
870	890	sand
890	1016	shale
1016	1410	soft sandy shale
1410	1545	shale
1545	1700	shale and shells
1700	1707	shale
1707	1737	anhydrite
1737	2645	shale and shells
2645	3000	shale
3000	3107	shale and lime
3107	3203	shale and
3203	3430	shale and lime
3430	3467	lime
3467	3530	lime and shale
3530	3671	lime
3671	3776	lime and shale
3776	3811	chert, sand and shale
3811	3847	conglomerate
3847	3910	cherty dolomite & conglomerate

- Topsoil 3415
- K.S. Brown 3426
- K.S. White 3432
- Loose K. O. 3479
- Conglomerate 3759
- Revered Arb. 3820
- Hard Arkuskie 3892


State of Kansas)
County of Sedwick) ss

I hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept on said well.

J. B. Hinkle

Subscribed to and sworn to before me this 21st day of December, 1947.

Murch O. Wolfe
Notary



Registration number 1-17-50

PLUGGING
FILE SEC-11 T-9 R-21W
BOOK PAGE-6 LINE-27

