

15-065-20609-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
Rev. 12/15/80

SEP 28 1982

CONSERVATION DIVISION
Wichita, Kansas

9-28-82

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 11 TWP. 9 RGE. 21W E/W
Location as in quarters or footage from lines:

SE NW SW

Lease Owner Sun Production Company

Lease Name Davignon #6 Well No. _____

Office Address P.O. Box 35567 Tulsa, Oklahoma 74135

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 9-20-82

Plugging completed 9-24-82

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel

Producing formation _____ Depth to top _____ bottom T.D. 3882'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	288'	none
				5-1/2"	3879'	1201'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Thick oil in hole, ran in 3500' of tubing and circulated well. Shot casing @3017', 2522', 2016', 1604' and 1200'. Pulled 3 joints of 5-1/2" and plugged well while coming out of the hole with the last 35 joints of pipe. At 1100', ran 2 sacks hulls and 100 sacks cement mixed with 1 sack hulls, @800', ran 100 sacks hulls, @500', ran 100 sacks hulls, @300', ran 150 sacks of cement mixed with 1 sack hulls,

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Plugging Complete

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 1982



My Commission expires:

Irene Hoover
Notary Public.