

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-20617-00-0

LEASE NAME V. Newell

WELL NUMBER 1

SPOT LOCATION 2310' FNL & 330'

SEC. 11 TWP. 9S RGE. 21 (X) or (W)

COUNTY Graham

Date Well Completed 7-25-73

Plugging Commenced 12-12-85

Plugging Completed 12-12-85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR CONOCO Inc.

ADDRESS 3817 N. W. Expressway
Oklahoma City, OK 73112

PHONE # (405) 948-3244 OPERATORS LICENSE NO. 5916

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6, 1014-Cody, Hayes, KS

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Penn Conglomerate Depth to top 3738' bottom 3802' T.D. 3859'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Shawnee	Oil	3180	3429	8 5/8"	257'	None
Lansing-KC	Oil	3429	3648	5 1/2"	3853'	None
Penn-Conglomerate	Oil	3738	3802			
Arbuckle	Oil	3802	TD			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. RU Welex and perforate 10 holes at 1050'.
Rig up Howco and pump 25 sacks of 60/40 POZ Mix with 10% gel and 2 sacks hulls down casing.
Pumped 100 sacks 60/40 POZ mix with 10% Gel and 2 sacks hulls down surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5447
Address 2707 Vine, Hayes, KS 67601

(913) 625-3931

STATE OF Oklahoma COUNTY OF Oklahoma, ss.


Sam White, Administrative Supervisor (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Sam White

(Address) 3817 N.W. Expressway

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 1986

RECEIVED
STATE CORPORATION COMMISSION
Notary Public



Expires: 4-29-89

DEC 26 1985

JAN 3 1986

CONSERVATION DIVISION CP-4
Revised 01-84

1-3-86