

API NUMBER 1506501028-00-26

LEASE NAME Darnell

WELL NUMBER #2

2310 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 21 TWP. 9 RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 6/16/50

Plugging Commenced 2/3/94

Plugging Completed 2/3/94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Arrowstar Prod Co.

ADDRESS PO Box 458 Ness City KS 67560

PHONE(S) (913) 798-3408 OPERATORS LICENSE NO. 3631

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/3/94 (date)

by Hays, KS (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation Arbuckle Depth to Top 3782 Bottom T.O. 3786

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		-0-	260'	8 5/8"	260'	-0-
		-0-	3780'	5 1/2"	3780'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Attempted washdown. Drilled cement to 820'. Couldn't drill deeper. With 2 3/8" tubing @ 820' Allied Cementing pumped down 2 3/8" tubing and circulated w/70 sx of 60/40 8% Gel w/50# bulls. Then Allied pumped down 8 5/8" x 5 1/2" annulus w/50 sx of 60/40 8% Gel w/50# bulls - Reached 300# Shut In @ 150# HWS pulled tubing from well. Allied squeezed 5 sx cement into 5 1/2" casing @ 300# Shut In @ 200# 3:45 PM

Name of Plugging Contractor Hembree Well Service Inc. License No. 6907

Address PO Box 458 Ness City KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Fred J. Hembree

STATE OF _____ COUNTY OF _____, ss.


Fred J. Hembree

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Fred J. Hembree

(Address) Ness City, KS 67560



AND SWORN TO before me this 28 day of March 1994

Phyllis M. Hembree
 Notary Public

My Commission Expires: May 15, 1996

USE ONLY ONE SIDE OF EACH FORM

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 30 1994
 CONSERVATION DIVISION
 WICHITA, KANSAS
 3-30-94