

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

20608  
00-00

API NUMBER 15-065-2608

LEASE NAME Davignon

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

WELL NUMBER 5

2385 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 11 TWP. 9 RGE. 21 (W)

LEASE OPERATOR Bowman Oil Co

ADDRESS 805 Codell Rd, Codell, Ks 67663

COUNTY Graham

PHONE# (785) 434-2286 OPERATORS LICENSE NO. 6931

Date Well Completed 6/12/73

Character of Well oil

Plugging Commenced 4/21/98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/21/98

The plugging proposal was approved on 3/25/98 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached?

Producing Formation Cong Depth to Top 3740 Bottom 3745 T.O. 3898

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cong	oil & water	3740	3745	8 5/8	283	none
				5 1/2	3898	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Perforated 1770 & 980, ran tubing to 2800 and spotted 150 sx cement w 3 sx hulls, pulled to 1400 and pumped 35 sx cement w/3 sx hulls, cement circulated, pulled tubing and tied onto 5 1/2, pumped in 25 sx to 300#, put 15sx cement & 1 hull in 8 5/8 & pressured to 750#

Name of Plugging Contractor Allied Cementing Inc License No. \_\_\_\_\_

Address Box 31, Russell, KS 67665


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bowman Oil Company

STATE OF Kansas COUNTY OF Rooks, ss.

Louis D Bowman (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Louis D Bowman

(Address) 805 Codell Rd, Codell, KS 67663



AND SWORN TO before me this 10<sup>th</sup> day of June, 19 98  
Jackie J. Langholz  
Notary Public

My Commission Expires: 2-24-2001  
USE ONLY ONE SIDE OF EACH FORM

REC'D 6-11-98