


15-065-01456-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Graham County, Sec. 21 Twp. 9 Rge. 21 xxx (W)
Location as "NE/CNW%SW%" or footage from lines SW/4 SE/4 NW/4
Lease Owner: Barnett Oil Company
Lease Name: Andreson "B" Well No. 5
Office Address: 411 First National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed July 15, 1950
Application for plugging filed Yes 19
Application for plugging approved Yes 19
Plugging commenced November 22, 1958
Plugging completed December 2, 1958
Reason for abandonment of well or producing formation Oil Depleted

If a producing well is abandoned, date of last production August 31, 1958
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3827 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	146 1/2'	-0-
				5 1/2"	3824'	1090'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3827'.
Plugging started 11-22-58. Finished 12-2-58.
Plugged off bottom and sanded back to 3820'. Dumped 5 sacks cement.
Worked and shot pipe. Shot 5 1/2" casing at 1,090'. Built rack and slide and layed down pipe. Plugged well as follows: Mudded to 145'.
Bailed down fluid, 10 ft. rock bridge at 145' and dumped 25 sacks cement. Mudded to 40'. Set rock bridge and mixed 10 sacks cement for cap on well. Well completed.

(Well Log attached)

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1958
CONSERVATION DIVISION
Wichita, Kansas

12-17-58

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
F. H. Rousey (employee or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Rousey
411 First Nat'l Bank Bldg., Wichita, Kansas (Address)



SUBSCRIBED AND SWORN to before me this 16th day of December, 1958.
My commission expires February 27, 1960.
Mildred J. Willis, Notary Public.

PLUGGING
FILE SEC 21 T 9 R 21W
BOOK PAGE 147 LINE 7

Barnett Oil Company, Hill City, Kansas
Andreson B-#5
SW/SE/NW 21-9-21W
Graham County, Kansas

Commenced: 6-16-50
Completed: 7-16-1950

Remarks: Ran 147' of 8 5/8" 21#
Casing-set @ 146.5
Cemented W/100 sacks cement
circulated.

DRILLERS LOG

Surface Clay	0-22
Sand	22-75
Shale and shells	75-130
Blue shale	130-147
Shale and shells	147-1150
Sand	1150-1350
Shale and shells	1350-1772
Anhydrite	1772-1811
Shale and shells	1811-2250
Shale and lime	2250-2360
Lime and shale	2360-3365
Lime	3365-3705
Lime and shale	3705-3824
Dolomite	3824-3827
Rotary T.D.	3827
Completed depth	3827
2' of open hole	

Ran 3825' of 5 1/2" S.S. 17# casing
set at 3825. Cemented with 125 sacks
common cement.

PLUGGING
FILE SEC. 21 T. 9 R. 21W
BOOK PAGE 147 LINE 7

RECEIVED
STATE CORPORATION COMMISSION

NOV 22 1958
CONSERVATION DIVISION
Wichita, Kansas

11-22-58