

15-065-02437-00-00

BARNETT-SHIELDS KIRKPATRICK # 1

WELL LOG

C NE $\frac{1}{4}$ NE $\frac{1}{4}$ SEC. 21-9S-21W, GRAHAM COUNTY, KANSAS

FORMATION	FROM	TO	REMARKS
Clay	0	20	
Sand & clay	20	153	Set 150' 8 5/8" Surface pipe
Shale	153	1195	Slope test @ 250' & 1000' S. L. M. @ 1022
Sand	1195	1365	
Redbed	1365	1450	
Shale & shells	1450	1700	
Anhydrite	1700	1725	
Shale & shells	1725	2315	
Shale & lime	2315	2405	
Lime	2405	2425	
Shale	2425	2515	
Shale & shells	2515	2580	
Shale & lime	2580	2630	
Shale & lime shells	2630	2680	
Shale & shells	2680	2795	S. L. M. @ 2721'
Lime & shale	2795	2910	Slope test @ 2850'
Shale & lime shells	2910	3020	
Shale	3020	3095	
Lime & shale	3095	3160	
Shale & lime shells	3160	3265	Slope test @ 3250'
Lime	3265	3410	S. L. M. @ 3380'
Lime & shale	3410	3450	
Lime	3450	3580	
Lime & shale	3580	3615	Mixed 300# Hulls
Lime	3615	3655	Circulated 2 hrs. @ 3655'
Lime & shale	3655	3668	Circulated 2 hrs. @ 3665'
Conglomerate	3668	3690	Circulated 1 1/2 hrs. @ 3690'
Shale & lime	3690	3725	Circulated 1 3/4 hrs. @ 3725'
Conglomerate	3725	3772	Slope test @ 3725'
Total depth		3772	Dry and abandoned

Commenced drilling - November 30, 1942
 Completed - December 11, 1942
 Contractor - Barnett Drilling Company

PLUGGING
 FILE SEC 21-T-9-R-21W
 BOOK PAGE 59 LINE 8a

DEC 2
 12-24-42