

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

**Locate well correctly on above
Section Plat**

Name of Conservation Agent who supervised plugging of this well.....M. A. Rives.....
Producing formation.....-..... Depth to top.....-..... Bottom..... Total Depth of Well 3821 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled hole with heavy mud from 3821 feet to 175 feet. Set plug at 175 feet and filled with cement to 128 feet. Filled surface casing with heavy mud from 128 feet to 34 feet. Set plug at 34 feet and filled casing with cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: Barnett Oil Company
Address: 417 First Nat'l Bank Bldg., Wichita, Kansas



STATE OF Kansas, COUNTY OF Sedgwick, SS
W. R. Hunter (employee of owner) ~~XXXXXX~~


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. /

(Signature)

First Nat'l. Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of August 19 48

My commission expires.....May 12, 1951



21-543-S

8-45--6M

Notary Public.



15-065-02481-00-0

BARNETT OIL COMPANY ET AL

LOG OF FELT WELL NO. 2

SE¹/₄ NE¹/₄ SE¹/₄ SECTION 21-9S-21W, GRAHAM COUNTY, KANSAS

Formation	From	To	Remarks
Surface Clay	0	40	
Sand	40	65	
Shale	65	129	Set 8 5/8" Surface Pipe at 128 feet, Cemented with 125 Sacks of Cement.
Shale and Shells	129	830	
Shale	830	900	
Sand and Shale Streaks	900	1050	
Shale	1050	1225	
Sand	1225	1480	
Shale	1480	1565	
Shale and Shells	1565	1735	
Anhydrite	1735	1767	
Shale and Shells	1767	1870	
Lime and Shale	1870	2270	
Lime	2270	2340	
Shale	2340	2475	
Lime and Shale	2475	2530	
Lime	2530	2565	
Sandy Shale	2565	2665	
Lime and Shale	2665	2900	
Lime	2900	2945	
Lime and Shale	2945	3085	
Lime	3085	3280	
Lime and Shale	3280	3360	
Lime	3360	3700	
Broken Lime	3700	3775	
Lime	3775	3821	
Total Depth		3821	Dry and Abandoned.



8-11-48