

15-065-62918-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Graham County. Sec. 21 Twp. 9 Rge. (E) 21 (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Barnett Oil Company
Lease Name Felt Well No. 1
Office Address 417 First Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed July 27, 1946
Application for plugging filed February 24, 1953
Application for plugging approved February 24, 1953
Plugging commenced February 24, 1953
Plugging completed March 6, 1953
Reason for abandonment of well or producing formation Production does not justify operation of the well
If a producing well is abandoned, date of last production January 8, 1953
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3775 Bottom 3781 Total Depth of Well 3781 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing		-0-	166 ft.	10 3/4"	166 ft.	None
Oil String		-0-	3777 ft.	5 1/2"	3777 ft.	1123 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with rock from 3781 feet to 3771 feet. Dumped four sacks of cement in casing from 3771 ft. to 3743 ft. Pipe shot off and pulled at 1123 feet. Filled with heavy mud from 3743 feet to 166 feet. Set rock bridge in surface pipe from 166 ft. to 163 ft. and filled with cement to 123 feet. Filled surface casing with heavy mud from 123 feet to 25 feet and with cement from 25 feet to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1953
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bert Self
Address R.R. #1, Hutchinson, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
W. R. Hunter (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. R. Hunter*
417 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of April, 1953
My commission expires February 27, 1956.
Mildred F. Willis
Notary Public.



24-2675-S 2-52-20M

PLUGGING
FILE SEC 21 T 9 R 214
BOOK PAGE 85 LINE 24

15-065-02918-00-00

BARNETT OIL COMPANY, ET AL
LOG OF FELT WELL NO. 1
NE¹/₄ NE¹/₄ SE¹/₄ SECTION 21-9S-21W
GRAHAM COUNTY, KANSAS

DATE COMMENCED: July 9, 1946

DATE COMPLETED: July 27, 1946

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface clay and shale	-0-	166	Set 10 3/4", 32.75# surface pipe at 166 feet; cemented with 125 sacks of cement.
Shale and shells	166	820	
Sand	820	1420	
Shale	1420	1662	
Shale and shells	1662	1705	
Anhydrite	1705	1733	
Shale	1733	1795	
Lime and Shale	1795	1833	
Shale	1833	1986	
Shale and Shells	1986	2010	
Lime	2010	2165	
Lime and Shale	2165	2320	
Lime	2320	2395	
Lime and Shale	2395	2530	
Lime	2530	2560	
Shale, lime and shells	2560	2750	
Iron and shale	2750	2753	
Shale and Lime	2753	2810	
Shale	2810	2895	
Lime	2895	2945	
Shale	2945	3045	
Lime and Shale	3045	3100	
Lime	3100	3228	
Lime and Shale	3228	3309	
Lime	3309	3365	
Shale	3365	3455	
Lime	3455	3645	
Lime and Shale	3645	3781	Set 5 1/2", 15# Casing at 3777 feet; cemented with 125 sacks of cement.
Total Depth		3781	

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1953

CONSERVATION DIVISION
Wichita, Kansas

4-11-53

PLUGGING

FILE SEC 21 T 9 R 21 W

BOOK PAGE 25 LINE 24