


18-065-03398-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217



Locate well correctly on above
Section Plat

Graham County. Sec. 21 Twp. 9 Rge. (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines. SE SW NW
Lease Owner Barnett Oil, Inc.
Lease Name Andreson "B" Well No. 6
Office Address 411 First National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil 67202
Date well completed April 13 19 51
Application for plugging filed August 27 19 74
Application for plugging approved _____ 19 _____
Plugging commenced September 24 19 74
Plugging completed October 15 19 74
Reason for abandonment of well or producing formation depleted
If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3826 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			137'	8 5/8"	137'	none
			3820 1/2'	5 1/2"	3820 1/2'	787.94

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3800' and dumped 5 sacks of cement.

Allied Cementing Company plugged well pumping in 5 sacks of hulls, 25 sacks of gel and 150 cubic feet of cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1974
CONSERVATION DIVISION
Wichita, Kansas

16-23-74

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 128, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of October, 19 74

JENNY KASSELMAN
NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY COMM. EXP. JULY 16, 1978

Jenny Kasselmann
Notary Public.

My commission expires _____

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

Wichita, Kansas

COPY

15-065-03398-00-00

Company - BARNETT DRILG. CO.
Farm - Anderson "B" No. 6

SEC. 21 T. 9 R. 21W
SE SW NW


Total Depth. 3826
Comm. 3-26-51 Comp. 4-13-51

County. Graham

Shot or Treated.

KANSAS

Contractor. Barnett Drilg., Inc.



Issued. 6-23-51

Elevation. 2305

Production. 168 BO & 22% wtr.

CASING:

8 5/8" 137' cem. w/125 sx
5 1/2" 3820 1/2' cem. w/125 sx

Figures Indicate Bottom of Formations.

surface clay	75
sand	85
shale, shells	137
shale	200
shale, shells	890
sand	1005
shale, shells	1130
sand	1190
shale & red rock	1545
shale, shells	1759
anhydrite	1796
shale, shells	2354
shale & lime	2475
shale, shells	2560
shale & lime	2635
shale & lime shells	2795
shale	2885
shale & lime	3395
lime	3826
Total Depth	

Scout Tops:	
Heebner	3465
Kansas City	3501
Arbuckle	3820

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1957
CONSERVATION DIVISION
Wichita, Kansas

8-24-74