

19-065-20282-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 10 Twp. 9S Rge. (E) 21 (W)

Location as "NE/CNWxSWx" or footage from lines NE SW NE  
Lease Owner Tilco etal  
Lease Name Desair Well No. 1  
Office Address P.O. Box 486 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed November 28 19 69  
Application for plugging filed November 28 19 69  
Application for plugging approved November 28 19 69  
Plugging commenced November 28 19 69  
Plugging completed November 28 19 69  
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	243'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

At 775' Plugged with 100 sacks 50/50 Pozmix 6% Gel  
At 275' Plugged with 25 sacks 50/50 Pozmix 6% Gel  
At 40' Plugged with 1/2 sack Hulls 10 sacks 50/50 Pozmix 6% Gel

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas

12-12-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lehen Drilling, Inc.  
Address P.O. Box 486, Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.  
James R. Rodgers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James R. Rodgers  
P.O. Box 486 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of December, 19 69

Helen L. Lindenmuth  
Helen L. Lindenmuth Notary Public.

November 13, 1973



15-065-20282-00-00

DRILLER'S LOG

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas

12-12-69

COMPANY:	Tilco et al
CONTRACTOR:	LEBEN DRILLING, INC.
FARM:	DESAIR #1
LOCATION:	NE SW NE SECTION 10-9S-21W GRAHAM COUNTY, KANSAS
COMMENCED:	11-20-69
COMPLETED:	11-28-69

---

0	45	Surface Clay & Post Rock
45	70	Post Rock
70	243	Shale Sand & Blue Rock
243	775	Shale
775	1335	Sand & Shell
1335	1638	Red Bed
1638	1673	Anhydrite
1673	1935	Shale
1935	2330	Shale, Lime Stks
2330	3215	Lime & Shale
3215	3780	Lime
	<u>3780</u>	<u>RTD</u>

---

8 5/8" 20# New Surface Casing set @ 243' cemented with 175 sacks  
Common 2% C.C.

I, James R. Rodgers, do hereby certify that the above and foregoing  
is a true and correct copy of the log of the Desair #1 Well, located  
NE SW NE of Section 10, Township 9 South, Range 21 West, Graham  
County, Kansas, as reflected by the records of Leben Drilling, Inc

*James R. Rodgers*  
James R. Rodgers

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in  
and for Barton County, Kansas, this 10th day of December, 1969.

*Helen L. Lindenmuth*  
Helen L. Lindenmuth

My Commission Expires:  
November 13, 1973

