

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-06520597 -00-00

LEASE NAME Loveridge

TYPE OR PRINT
NOTICE: Fill out completely
and return to GORS. Div.
office within 30 days

WELL NUMBER 6

2310 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR Phillips Petroleum Company

SEC. 10 TWP. 9 RGE. 21 (E) or (W)

ADDRESS 510 N.W. 3rd, Plainville, Kansas 67663

COUNTY Graham

PHONE # 913) 434-4638 OPERATORS LICENSE NO. 5229

Date Well Completed 04/16/73

Character of Well OIL

Plugging Commenced 06/19/95

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 06/19/95

The plugging proposal was approved on Verbal approval by Dennis Hamel 06/16/95 (date)

by Dennis Hamel (KCC District Agent's Name)

is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation LKC and Arbuckle Depth to Top 3404' Bottom 3770' T.D. 3818'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	267'	0'
				5 1/2"	3817'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

Perf. 4 holes @ 960'. Circ. csg full of cmt from 3330' to surf. in 1000' stages, while laying down 1000' of tbg between stages. Cmt slurry consisted of 60-40 pozmix with 10% gel. After csg full of cement, pumped an additional 28 sx of cmt out of holes at 960'. Press to 300# and S.I. Conn to 8 5/8 x 5 1/2 annulus pmpd 55 sx w/100# hulls, press to 300# S.I. Total cmt 325sx

Name of Plugging Contractor Phillips Petroleum Company License No. 5229

Address 510 N.W. 3rd, Plainville, Kansas 67663

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Phillips Petroleum Company


JUN 21 1995

STATE OF Kansas COUNTY OF Graham, ss.

B-21-95

David J. Stahl (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONCESSION DIVISION
WICHITA, KANSAS



(Signature) D. J. Stahl

(Address) 510 N.W. 3rd, Plainville, Kansas 67663

SUBSCRIBED AND SWORN TO before me this 20 day of 06, 19 95

My Commission Expires: 6-7-98
Mary Augustine
Notary Public

USE ONLY ONE SIDE OF EACH FORM