

15-065-01492-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER compl 10/43

LEASE NAME Barry Flora Barry

WELL NUMBER 1 ^{KCC} _{ZAP}

SPOT LOCATION NW SW SW

SEC. 24 TWP. 9S RGE. 21W (E) or (W)

COUNTY Graham

Date Well Completed 10/43

Plugging Commenced 9/30/87

Plugging Completed 9/30/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

PHONE # () 267-3241 OPERATORS LICENSE NO. 6033

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? no If not, is well log attached? yes

Producing formation Tor/LKC/Arb Depth to top 3441' bottom 3740' T.D. 3752'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4"	275'	-
				5 1/2"	3769'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped 5 sx. hulls + 200 sx. Econolite down 5 1/2" csg. Max 125 psig, ISIP 50 psig. Backside full of cmt. Test 100 psig - held. Approved by Carl Goodrow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033
Address 250 N. Water, Suite 300; Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick

OCT 30 1987
10-30-87
CONSERVATION DIVISION
Wichita, Kansas

Larry M. Jack, Eastern Div., Prod. Mgr. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, I have knowledge of the facts, statements, and matters herein contained in the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) By: Larry M. Jack
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 29 day of Oct, 1987

Kerran Redington
Kerran Redington
Notary Public



My Commission expires: 2/6/90

18-065-01492-00-00

THE BRITISH-AMERICAN OIL PRODUCING COMPANY

WELL LOG - FLORA BARRY NO. 1

LOCATION: 990' from the South line and 330' from the West line of the SW/4 of Section 24-9S-21W, Graham County, Kansas.

Ground Elevation	2249'
Total Depth	3772'
Top Arbuckle Lime	3768' (-1519')
Initial Potential (Physical test on pump)	194 oil, no water
Drilling Commenced	10-3-43
Drilling Completed	10-22-43

CASING RECORD: 10-3/4" OD surface casing cemented at 271' with 100 sacks.
 5-1/2" OD oil string casing cemented at 3769' with 250 sacks.

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
0	50	Sand		
50	130	Shale & sand		
130	285	Shale & shells		
285	600	Shale & sand		
600	705	Sand & shells		
705	875	Shale, sand & shells		
875	1020	Sand & shale		
1020	1195	Sandy shale		
1195	1255	Red rock & shale		
1255	1475	Sand & shale		
1475	1700	Shale & shells		
1700	1770	Anhydrite		
1770	1815	Shale		
1815	1905	Red bed shale & shells		
1905	2545	Shale & shells		
2545	2607	Shale & lime		
2607	2780	Shale		
2780	2950	Shale & lime		
2950	3042	Shale and shells		
3042	3483	Shale & lime		
3483	3665	Lime		
3665	3756	Lime & chert		
3756	3768	Shale & lime		
3768	3772	Sandy shale		
3772	3776	Lime (show of oil). Top Arbuckle 3772'.		
	3772	Total depth corrected to ground level.		

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1987

CONSERVATION DIVISION
Wichita, Kansas