

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-179-20,820-00-00

LEASE NAME Taylor "B"

WELL NUMBER #1

3300 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 24 TWP. 8S RGE. 27 (W)

COUNTY Sheridan

Date Well Completed 7-12-85

Plugging Commenced 7-12-85

5:30 A.M.
 Plugging Completed 7-12-85

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Sunburst Exploration Company, Inc.

112 Corporate Place

ADDRESS 125 North Emporia, Wichita, KS 67202

PHONE#(316) 262-3041 OPERATORS LICENSE NO. 5005

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6 - David Wann

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.D. 3965'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	247'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

- Plug #1 @ 2195' w/20 sks. cement
 - Plug #2 @ 1315' w/100 sks. cement
 - Plug #3 @ 300' w/40 sks. cement
 - Plug #4 @ 40' w/10 sks. cement, 10 sks. cement in rathole
- (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor John O. Farmer, Inc. License No. 5135

Address P.O. Box 352, Russell, KS 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ronald L. Irion (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Ronald L. Irion

(Address) 112 Corporate Place
125 N. Emporia

RECEIVED
 STATE CORPORATION COMMISSION

FILE 1 OF
 n-19-85

CONSECRATED AND SWORN TO before me this 18th day of July, 19 85



Julie K. Polczynski
 Julie K. Polczynski Notary Public
July 23, 1985

15-179-20820-00-00

JOHN O. FARMER, INC.

OIL PRODUCERS AND DRILLING CONTRACTORS

BOX 352

RUSSELL, KANSAS 67665

913-483-3144

WELL LOG

Operator: Sunburst Exploration Company, Inc.

Contractor: John O. Farmer, Inc.

Well & Well Description: Taylor "B" #1
C S/2 NE Sec. 24-8S-27W, Sheridan County, Kansas

Commenced: July 5, 1985

Completed: July 12, 1985

Character of Well: D & A

Elevation: 2556' K.B. 60/40

Casing: 8-5/8" set @ 247' w/150 sks. Pozmix (3% C.C., 2% gel)

Figures Indicate Bottom of Formations

Sand & Clay	120'
Blue Shale	249'
Shale & Sand	1810'
Sand	1980'
Red Bed	2195'
Anhydrite	2231'
Shale & Shells	2730'
Shale	3415'
Shale & Lime	3580'
Lime	3965'

RECEIVED
STATE CORPORATION COMMISSION

FRI-1 9 1985
CONSERVATION DIVISION
Wichita, Kansas

7-19-85

State of Kansas)
County of Russell) SS.

I John O. Farmer, president of JOHN O. FARMER, INC.

upon oath state that the above and foregoing is a true and correct copy of the log of the Taylor "B" #1 well.

John O. Farmer
John O. Farmer

Subscribed and sworn to before me this 17th day of July, 19 85.

Margaret A. Schulte
Margaret A. Schulte - Notary Public

