

15-177-00150-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Sheridan County, Sec. 25 Twp. 8S Rge. 27W (E) (W)

Location as "NE/CNW%SW%" or footage from lines C NE SE

Lease Owner Leben Drilling, Inc.

Lease Name Willie Brown Well No. 1

Office Address 905 Central Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-6-59 19

Application for plugging filed 12-6-59 19

Application for plugging approved 12-6-59 19

Plugging commenced 12-6-59 19

Plugging completed 12-6-59 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3990 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT.
				8 5/8	209	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug set @ 500' w/ 20 sx. cement.

2nd plug set @ 200' w/ 20 sx. cement.

Top plug set @ 40' w/ 10 sx. cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address 905 Central Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Frank Hamlin

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin

905 Central Bldg., Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 19 59

My commission expires April 23, 1963

Juanita M. Green Notary Public.



15-179-00150-0000

DRILLER'S LOG

COMPANY:	LEBEN DRILLING, INC.
CONTRACTOR:	LEBEN DRILLING, INC.
FARM:	WILLIE BROWN #1
LOCATION:	C NE SE SEC. 25-8S-27W SHERIDAN COUNTY, KANSAS
COMMENCED:	11-28-59
COMPLETED:	12-6-59

0	60	Surface Soil and Clay
60	209	Sand and Shale and Shells
209	600	Blue Shale
600	1310	Shale
1310	1665	Shale
1665	1830	Shale and Shells
1830	2205	Redbed and Shale
2205	2230	Redbed and Shale
2230	2265	Anhydrite
2265	2465	Shale
2465	2640	Shale and Lime
2640	2655	Lime and Shale
2655	2940	Lime and Shale
2940	3235	Lime and Shale
3235	3480	Shale and Lime
3480	3610	Shale and Lime
3610	3690	Lime and Shale
3690	3760	Shale and Lime
3760	3845	Lime and Shale
3845	3895	Lime
3895	3935	Lime
3935	3990	Lime and Shale
	<u>3990</u>	<u>Rotary Total Depth - D & A</u>

RECEIVED
 CONSERVATION COMMISSION
 DEC 18 1959
 CONSERVATION DIVISION
 Wichita, Kansas
 12/18/59

Set 8 5/8" surface casing @ 209' with 150 sacks Sunset cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Willie Brown #1, located C NE SE of Section 25, Township 8 South, Range 27 West, Sheridan County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin


 Frank Hamlin

STATE OF KANSAS)
 COUNTY OF SEDGWICK) ss.

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 16th day of December, 1959.

Juanita M. Green

 Juanita M. Green, Notary Public



My Commission Expires:
 April 23, 1963