

15-179-20608-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY SHERIDAN SEC. 25 TWP. 8 RGE. 27 NW
Location as in quarters or footage from lines:

SEC. 25

SE - NE - NE

				①

Locate Well
correctly on above
Section Platt.

Lease Owner LOCHIEL EXPLORATION LTD.
Lease Name BROWN PROSPECT Well No. 2
Office Address 1106 333-5 AVE. S.W.
CALGARY, ALBERTA, CANADA T2P 3B6
Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE
Date Well Completed JULY 31, 1981
Application for plugging filed JULY 29, 1981
Plugging commenced JULY 31, 1981
Plugging completed JULY 31, 1981
Reason for abandonment of well or producing formation NO

INDICATION OF COMMERCIAL HYDROCARBONS

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well M. SCHMIDT

Producing formation - Depth to top - bottom - T.D. 3990'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>LOCAL AQUIFER</u>	<u>FRESH WATER</u>	<u>0</u>	<u>266'</u>	<u>8 3/8</u>	<u>YES</u>	<u>NO</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUG #1: EQUALIZED AT BOTTOM OF DRILL PIPE AT 1250', 60 SACK 1:1 POZMIX PWS
6% GEL, USING MUD FOR DRILL PIPE DISPLACING. (PLUG FROM 1000'-1250')

PLUG #2: EQUALIZED AT BOTTOM OF DRILL PIPE AT 250', 30 SACK 1:1 POZMIX PWS
6% GEL, USING MUD FOR DRILL PIPE DISPLACING. (PLUG FROM 150'-250')

PLUG #3: PUSHED RUBBER WIPER PLUG TO 40' KB. DUMPED 10 SACK 1:1 POZMIX PWS
6% GEL ON TOP OF PLUG. HAD CEMENT TO SURFACE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SUN OIL WELL CEMENTING INC.

STATE OF Kansas COUNTY OF Graham, ss.
GARRY S. HAMILTON, C.E.T. (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature] C.E.T.
31 LAWRENCE CRESCENT
ST. ALBERT, ALBERTA CANADA



TO before me this 3rd day of August, 19 81

George Mensley
Notary Public

My Commission expires: March 23, 1985

RECEIVED
STATE CORPORATION COMMISSION

AUG 6 1981 8/6/81
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202

15-179-20608-00-00

INVOICE and WELL PLUGGING AUTHORITY

INVOICE NUMBER: 7627-W

September 28, 1981

TO: ~~Lochiel Exploration, LTD~~
~~1106, 333-5 th Ave. S. W.~~
~~XXXXXX Calgary, Alberta, Canada T2P 3B6~~

PLUGGING ASSESSMENT AS FOLLOWS: PAYABLE UPON RECEIPT


Brown #2
SE NE NE, Sec. 25-8S-27W
Sheridan
3825'

NOTE: We also need the following before our file is completed: \$124.31

- Well Plugging Record (CP-4)
- Well Log
- Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:
This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.
This authority is void after ninety (90) days from the above date.



For Administrator

~~Mr. Gilbert Balthazor, Box 9, Palco., KS. 67657~~
is hereby assigned to supervise the plugging of the above mentioned well.
RETURN PINK COPY WITH REMITTANCE