


15-179-00001-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Sheridan County. Sec. 26 Twp. 8S Rge. (E) 27W  
Location as "NE/CNW/SW" or footage from lines. SW/4 NW/4  
Lease Owner Heathman Oil  
Lease Name Brown "A" Well No. 2  
Office Address 1019 East Second, Wichita 7, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 5 19 58  
Application for plugging filed (Verbal approval rec'd) 19  
Application for plugging approved (Verbal approval rec'd) 19  
Plugging commenced February 5 19 58  
Plugging completed February 5 19 58  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabracius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4385 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	286	8-5/8"	286'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole with 25 sacks cement on bottom plug set at 550';  
15 sacks cement on middle plug set at 290'; 10 sacks cement on top plug set at 40'. - All cement mixed and spotted at above depths mentioned by Sun Cementing Co., ordered by State Plugger, A. D. Fabracius.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 13 1958

CONSERVATION DIVISION  
Wichita, Kansas

273-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Birmingham-Bartlett Drilling Co.  
Address 300 Kaufman Building, Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK  
Richard Hindery, partner of Birmingham-Bartlett Drilling Co., contractor of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BIRMINGHAM-BARTLETT DRILLING CO.

(Signature) \_\_\_\_\_ By: \_\_\_\_\_  
300 Kaufman Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of February, 19 58.

My commission expires November 29, 1958.

Vivian F. Yinger, Notary Public.



PLUGGING  
FILE SEC. 26T 8 R 276  
BOOK PAGE 81 LINE 33

BROWN "A" #2 WELL

LOCATION: SW/4 NW/4 Sec. 26-28-27W  
 Sheridan County, Kansas

OWNER and OPERATOR: Beatman Oil  
 1017 East Second  
 Wichita 7, Kansas

CONTRACTOR: Birmingham-Bartlett Drilling Co.  
 300 Kaufman Building  
 Wichita 2, Kansas

SURFACE CASING: 8-5/8" surface casing set at 236'  
 with 200 sacks cement and 4 c.c.

OIL STRING: None Set. Dry and Abandoned.

SPUDDED: 1-20-58  
 COMPLETED: 2-5-58

LOG

(Figures indicate bottom of formation)

C - 50	Clay and Sand
1206	Shale and Shells
1735	Shale, Shells and Sand
2160	Shale and Shells
2230	Red Bed and Shale
2265	Anhydrite
2555	Shale and Shells
2890	Shale and Lime
3040	Shale
3665	Lime and Shale
4035	Lime
4365	Lime and Shale
4385	Mississippi Chert
4385	Rotary Total Depth

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the Brown "A" #2 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn to before me this 7th day of February, 1958.

Vivian F. Yinger  
Vivian F. Yinger, Notary Public

My commission expires November 29, 1958.

2-13-58

REC-267 8 27W  
BLK PAGE 8 / LINE 33