

15-179-20184-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Sheridan County, Sec. 26 Twp. 8 Rge. (E) 27 (W)

Location as "NE/CNW/SW" or footage from lines C SW SE
Lease Owner Richard G. Smith
Lease Name Hill Well No. 1
Office Address 602 Rule Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Feb. 10, 1969
Application for plugging filed Feb. 13, 1969
Application for plugging approved Feb. 10, 1969
Plugging commenced Feb. 10, 1969
Plugging completed Feb. 10, 1969
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3975 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	246'	8-5/8"	246'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 1140 ft. Set first plug @ 1140 ft. w/100 sacks cement.
Filled hole with heavy mud to 275'. Set second plug @ 275 ft. w/20 sacks cement.
Filled hole with heavy mud to 40 ft. Set third plug @ 40 ft. w/10 sacks cement.
Plugged rat hole w/2 sacks cement. Job complete at 4:30 PM, 2/10/69. Job by Halliburton.

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1969
CONSERVATION DIVISION
Wichita, Kansas

2-17-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place - Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

830 Sutton Place - Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of February, 19 69



Barbara J. Layton
Barbara J. Layton Notary Public.

15-179-20184-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

HILL #1
C SW SE Section 26-8S-27W
Sheridan County, Kansas

Commenced: February 2, 1969
Completed: February 10, 1969

OPERATOR - Richard G. Smith

DEPTH		FORMATION	REMARKS
From	To		
0	246	Shale and sand	Ran 12 joints of 8-5/8" casing, set @ 246' w/225 sacks cement.
246	1950	Shale	
1950	2097	Red bed and shale	
2097	3165	Shale and lime	
3165	3302	Shale	
3302	3690	Shale and lime	
3690	3775	Lime	
3775	3820	Lime and shale	
3820	3825	Lime	
3825	3975	Lime and shale	
3975	TD		Dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1969
CONSERVATION DIVISION
Wichita, Kansas
2-17-69

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C SW SE Section 26-8S-27W, Sheridan County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 13 day of February, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public

