

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-179-05234-00 00

WELL PLUGGING RECORD

NORTH

			X

Locate well correctly on above
Section Plat

Sheridan County. Sec. 27 Twp. 8S Rge. (E) 27 (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner The Carter Oil Company

Lease Name Helen Karnes Well No. 1

Office Address Box 786, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed October 10 19 56

Application for plugging filed May 29 19 59

Application for plugging approved June 4 19 59

Plugging commenced June 4 19 59

Plugging completed June 8 19 59

Reason for abandonment of well or producing formation Uneconomical to produce

If a producing well is abandoned, date of last production May 20 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricus

Producing formation Kansas City Depth to top 3879 Bottom 3904 Total Depth of Well 3988 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City		3879	3904	8-5/8"	318'	0
				5-1/2"	4022'	1483'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand from 3988' to 3685', 3 sacks cement 3685' to 3664', mud 3664' to 315', rock 315' to 305', 25 sacks cement 305' to 230', mud from 230' to 40', rock from 40' to 30' & 25 sacks cement from 30' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 24 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address 1316 Hoover, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Hugh H. Goerner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Hugh H. Goerner
HUGH H. GOERNER, District Superintendent
Box 786, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 19 59.

My commission expires 8-19-61

William H. Knisley
William H. Knisley
Notary Public.

PLUGGING
FILE SEC 2218 R224
BOOK PAGE 41 LINE 45

15-179-05234-0000

GABBERT-JONES DRILLING CO., INC.
WICHITA, KANSAS
DRILLER'S WELL LOG

HELEN KARNES #1
NE NE NE SECTION 27-8-27
SHERIDAN COUNTY, KANSAS

COMMENCED 8-27-56
COMPLETED 9-7-56

DEPTH		FORMATION	REMARKS
FROM	TO		
0	72	SAND	
72	140	SAND & SHALE	
140	315	BLUE SHALE	RAN 315' OF 8 5/8", CEMENTED W/200 BAGS CEMENT, 2% CC.
315	413	SHALE	
413	1108	SHALE & SAND	
1108	1168	SAND	
1168	1550	SHALE	
1550	1640	SHALE & SHELLS	
1640	1730	ANHYDRITE	
1730	1805	SHALE & SHELLS	
1805	1985	SAND & SHALE	
1985	2125	SHALE & SHELLS	
2125	2170	SHALE	
2170	2210	ANHYDRITE	
2210	2425	SHALE & SHELLS	
2425	2735	LIME & SHALE	
2735	3580	LIME	
3580	3680	SHALE & LIME	
3680	3910	LIME	
3910	3988	LIME & SHALE	
3988		TD	RAN 3987' OF 5 1/2" CASING, CEMENTED @ 3987' W/225 BAGS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1959

CONSERVATION DIVISION
Wichita, Kansas

b/l/s

I E.E. HALL, CERTIFY THIS TO BE A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE HELEN KARNES #1.

STATE OF KANSAS)
COUNTY OF SEDGWICK)

SS

BEFORE, ME THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 10th DAY OF September, 1956 PERSONALLY APPEARED E.E. Hall TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FORGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES 10-29-57

Barbara Oldfield
NOTARY PUBLIC

PLUGGING
FILE SEC. 27 & R274
BOOK PAGE 4 / LINE 45