

API NUMBER 15-179-20081-00-01

LEASE NAME West Hoxie

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER M-2

990 Ft. from N Section Line

330 Ft. from E Section Line

SEC. 34 TWP. 08 RGE. 29 (E) or (W)

COUNTY Sheridan

Date Well Completed 4/5/68

Plugging Commenced 7/30/91

Plugging Completed 7/31/91

LEASE OPERATOR Koch Exploration Co.

ADDRESS P.O. Box 2256 Wichita, Kansas 67201

PHONE#(316) 832-5077 OPERATORS LICENSE NO. 6477

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 17, 1991 (date)

by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing/Kansas City Depth to Top 3930' Bottom 4172' T.D. 4220'

Show depth and thickness of all water, oil and gas formations.

9/13/91
 RECEIVED

OIL, GAS OR WATER RECORDS | CASING RECORD | STATE COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	226	None
				4 1/2	4219	None

SEP 13 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
RU Great Guns. RIH & Perf 2 holes @ 2450', 2 holes @ 1600'. RU Howco. pump 500# hulls,
225sx 65-35% Posmix w/10% gel, 5 BPM @ 400#, Pump 81 Bbl Press MC to 1000#, held 150#, Pump
100 sx 65-35% posmix w/10% gel, 1 BPM @ 100# on annulus, Press. csg to 500#. SI
P&A Complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Koch Exploration Co.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Kenneth Seymour (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kenneth Seymour

P.O. Box 2256

(Address) Wichita, KS 67201

SUBSCRIBED AND SWORN TO before me this 12th day of September, 19 91

My Commission Expires: _____

